

**Client:** Hobson & Porter

**Programme:** 26 Weeks

**Value:** £106,000

### Client's Requirements

Hobson & Porter required an experienced & reliable Groundworks contractor to take on and deliver a substantial Groundworks package on a new development of sustainable housing in the East Yorkshire village of Newport.

### Yorkshire Groundworks Contribution

Our Groundworks package included:-

**Drainage** From 150mm Supersleve up to 750mm concrete pre cast pipes laid up to 5m deep, including use of pipe lasers to assist in laying and drag boxes to shore up the excavations. Construction of a hydrobrake by manufacturing a bespoke shutter to fit the design & use of vertform® to cast the deep concrete manholes.

**Externals** laying of over 400m of kerbing around site, building hardcore base & paving to paths & patios to 18 (Phase 1 only) properties. Shuttering & casting concrete in situ for 1 shed base per each property as part of the code for sustainable homes. Forming up the surface to underside of tarmac areas to precise levels set out in partnership with our client.

**Services** Excavation & laying ducting for various services up to properties, Electric, Gas, Water & Communications.

### Client Feedback

Yorkshire Groundworks working in close partnership with Hobson & Porter were able to deliver the project ahead of programme.

“Yorkshire Groundworks have carried out the works to the standard set within our programme”

*Brian Wilson, Site Manager for Hobson & Porter.*

