

Client: Voase Builders Ltd

Programme: 4 Weeks

Value: £40,000

Client's Requirements

Voase Builders Ltd required a trusted reliable sub-contractor to procure, manage & deliver the construction of emergency access road to Beverley High School, this involved using a material called 'tech turf' to provide a hard wearing but green surface capable of withstanding loads from heavy traffic such as fire trucks.

Delivery

YGS Ltd were appointed to procure the materials, manage the job from start to finish (including erecting, maintaining & dismantling a site compound) & construct the roadway.

Yorkshire Groundworks Contribution

Our Groundworks package included:-

- Excavation** Excavate & cart away spoil off site to accomodate roadway construction.
- Sub-Base** Introduce & compact stone layer to underside of tech turf to take part of the loading & provide stability.
- Tech Turf** Lay Geotextile membrane then tech turf material with compost layer for root zone of the grass.
- Turf** Lay & water in turf layer to the top of the roadway.

Client Feedback

Bespoke, Personal, Professional; By showing strong leadership & organisational skills YGS Ltd were able to deliver a top quality surface using a new material to meet the clients specific requirements.

